

WATER SMART INDUSTRIAL SYMBIOSIS

D1.2 Operational demo cases CS7 Tain

UCRAN, Aquabio





Lead partner:



Other partner:




With support of:






PROCESS ₩₽ PROCESS AGRICULTURI NUTRIENTS / FOOD / MATERIAL NUTRIENTS / MATERIAL 111 INDUSTRY MAS NEXUS WATER (FOOD) INDUSTRY ELECTRICITY / CONSUMER







CS7: Objectives of the Ultimate solutions






CS7: Subtask 1.2.6 status/progress

Subtask: 1.2.6 RO treatment of distillery wastewater after AnMBR for internal water reuse Baseline technology: no water reuse so far (discharge of AnMBR effluent to Dornoch Firth)

Ultimate solution to foster circular economy: RO system for distillery wastewater (AnMBR effluent)



TRL: $5 \rightarrow 7$

Capacity of demo plant: 1 m³/d

Quantifiable target: At full scale, potential for the production of 58,000 m³/a for internal water reuse; >40 % reduction of freshwater through reuse of treated water

Status/progress:

- detailed design completed
- system available but needs adapting to fit latest configuration

CS7: Pictures of the new technologies

Subtask: 1.2.5 RO treatment of distillery wastewater after AnMBR for internal water reuse






The RO unit is designed to achieve high quality water for reuse from the distillery wastewater after treatment through a preprecipitation stage and ammonia stripping.






Subtask: 1.2.5 RO treatment of distillery wastewater after AnMBR for internal water reuse



 \rightarrow Pilot system expected to be operational in July 2022 (M26)

→ Still enough time to complete the pilot experiments






CS7: Subtask 1.3.5 status/progress

Subtask: 1.3.5 Heat recovery from treated (AnMBR) distillery wastewater Baseline technology: Biogas production via existing AnMBR; no heat recovery before Ultimate

Ultimate solutions to foster circular economy: heat recovery from the AnMBR effluent via heat exchangers



TRL: $5 \rightarrow 7$

Capacity of demo plant: heat utilization will be tested in all systems at 1 m3/d for the RO and 12 m3/d for the nutrients recovery

system and 14 kW of heat recovery can be expected

Quantifiable targets: At full scale, >15 % reduction of energy demand from biogas and 60 % heat recovery within stripping column unit


Status/progress:

- detailed design completed
- parts ordered

CS7: PID of the heat exchanging unit

Subtask: 1.3.5 Heat recovery from treated (AnMBR) distillery wastewater

P&ID of the heat exchange unit




The heat exchanger units are designed to maximise heat utilisation from the effluent after the ammonia stripping process.



CS7: First results of the new technologies

Subtask: 1.3.5 Heat recovery from treated (AnMBR) distillery wastewater


The biogas produced in the AnMBR first goes through a scrubber for H_2S removal and is then converted to steam in a boiler. The steam produced is reused to heat the stills in the distillery and contribute to reduce its dependence on fossil fuel by 15%.








Subtask: 1.3.5 Heat recovery from treated (AnMBR) distillery wastewater



 \rightarrow Heat recovery system expected to be operational in July 2022 (M26)

→ Still enough time to complete the pilot experiments






CS7: Subtask 1.4.6 status/progress

Subtask: 1.4.6 Recovery of ammonia from distillery wastewater via IEX/packed columns after AnMBR Baseline technology: reuse of digestate on the barley fields

Ultimate solution to foster circular economy: air stripping column & scrubber; struvite precipitation



TRL: $5 \rightarrow 7$ (air stripping column & scrubber); $5 \rightarrow 7$ (struvite precipitation)

Capacity of demo plants:12-24 m³/d


Quantifiable target: At full scale, potential for the production of 122 t struvite/a from the pre-precipitation stage and 47 t nitrogen/a from ammonia stripping, corresponding to about 80% P recovery and 80% N recovery in total

Status/progress:

- detailed design completed
- parts ordered

CS7: Results of the preliminary evaluation

Subtask: 1.4.6 Recovery of ammonia from distillery wastewater via IEX/packed columns after AnMBR




The evaluation of current knowledge and performance (see figure on the right) of ion exchange, stripping and precipitation based systems for ammonia recovery form industrial wastewaters and the measured characteristics of the anaerobically treated distillery wastewater led to the selection of a two-stage system comprising pre-precipitation (struvite) followed ammonia stripping to maximize the recovery of nutrients.



CS7: Pictures of the struvite precipitator

Subtask: 1.4.6 Recovery of ammonia from distillery wastewater after AnMBR



P&ID and drawing of the of the pre-precipitation reactor



The project leading to this application has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 869318

The pre-precipitation stage will act as pre-treatment to maximize ammonia recovery in the subsequent stripping unit while also recovering P and N in the form of struvite.

CS7: PID of the ammonia stripping unit

Subtask: 1.4.6 Recovery of ammonia from distillery wastewater after AnMBR

CRANKER BLACK IT SHE - serr 1.41 ----in still h - m³ 10.00 AND INCOME.


The stripping unit is designed to maximize the recovery of ammonia from the anaerobically treated distillery wastewater in the form of either an ammonia solution or ammonium sulphate.

P&ID of the ammonia stripping unit





Subtask: 1.4.6 Recovery of ammonia from distillery wastewater after AnMBR



→ Nutrients recovery system expected to be operational in July 2022 (M26)

→ Still enough time to complete the pilot experiments

Legend Task/Subtask Activity as planned Postponed activity Delay of activity





CS7 Contacts

m.pidou@cranfield.ac.uk M.M.Gritti@cranfield.ac.uk



